

ORDERING GUIDE – CONCRETE WALL PANELS

Pre-cast lightweight concrete panels applied to walls. Suitable for non-combustible interior and exterior applications.

Specifications

- 5/8" (16 mm) material thickness
- Naturally lightweight
- High-performance fiber-reinforce concrete

Textures/Colours

- Smooth – a polished matte finish
- Distressed – a weathered matte finish
- Raw – a natural finish with bug holes
- Board Formed – a wood grain finish

Sizes

- Custom panel sizes available within limitations
 - Smooth: Maximum length of 94" (2388 mm)
Maximum width: 58" (1473 mm)
 - Distressed, Raw and Board Formed: Maximum length of 94" (2388 mm)
Maximum width of 46" (1168mm)

Weight

- Maximum recommended size per panel: 16 Sq.Ft.
- At a consistent 5/8" material thickness, our panels weigh approximately 3.28 Kg/Sq.Ft. (7.22 Lbs/Sq.Ft.)

The Process

01
Quote

All panels are made to order and hand-cast to your specific requirements.

The following information is required to provide a formal quote:

- Approximate panel size(s) and quantities
- Shipping address

Please email info@anthonyconcretedesign.com

02
Accept

Accepting your formal quotation will serve as confirmation to move forward with processing your order and sending you concrete samples of colours and textures.

03
Finalize

Once payment is received, colour and texture are chosen, and the panel size(s) and quantities have been confirmed, we will provide you with design drawings for you to review and approve prior to moving your project into fabrication.

04
Fabrication

Typical fabrication lead times vary, and your formal quotation will outline the current lead time for your order. Lead times vary and are determined by the projects in the production queue at the time of ordering.

05
Crating / Shipping

All panels will be shipped in a made-to-fit wooden crate.

06
Receive Shipment

Residential orders are delivered curbside by appointment. Any shipment over 84”L may require a forklift on site to remove it from the shipping truck. The client is responsible for confirming and/or arranging the carrier's receipt of goods and for the cost of the forklift or other materials required for delivery.

07
Install

We recommend hiring a local stone installer or contractor who is comfortable and experienced working with stone and/or concrete materials.

08
Enjoy

Enjoy your new concrete panels and embrace its natural properties.